



City of Sycamore 2023 Sewer Lining Project

Addendum #3

February 27, 2023

1 Page

This addendum is issued for the purpose of clarifying the intent of the contract documents and plans and also for making necessary corrections, deletions, and/or additions to the documents and plans. This addendum shall supersede any information found with the Contract Documents, Plans or previous addenda.

Each proposer shall include this document into their proposal along with entering the information and signing below.

Company

Signature of Authorized Personnel

Date

1. Addendum 2 shall be corrected to read as follows.

Sanitary and Storm Sewer Lining within the Downtown area as identified by Locations 1-11 shall conform to the original requirements for Sanitary and Storm Sewer Lining and are now identified as "Pressure Rated" within the Schedule of Prices.

Pressure testing shall be a cured-in-place liner meeting the IEPA Requirements for watermain and storm sewer separation. The liner must be a structural liner meeting ASTM F1216. See the following page for IEPA Requirements (See Addendum #2).

The liner must be pressure tested to the maximum expected surcharge of the sewer ~~and must be rated for water main pressures.~~

All other locations are identified as "Standard" are not required to be pressure tested.

Storm Sewers can be visually inspected in lieu of a post video inspection.